






During the rainy season, the department of chemistry uses rainwater to lessen the burden on the water provided by the Municipal corporation. The flow of terrace water during the rain turned to the main tank by pipe and we use it for the departmental daily use. This is a small attempt to conserve water.







College has dug two wells to meet the daily water needs of the institution. The location of the wells is where the flow of rainy water percolates the adjoining place of the wells. We get perennial water from there. This is probably because of a small initiative to conserve water.





The college has installed a water sprinkler system for decoration purposes but it has been taken utmost care to reuse of water.



On

#### RAIN WATER HARVESTING SCHEME

For

## Institutional Building

Arts Science & Polytechnic Workshop Buildings, S. No. 20, 21 (P), 22 & 23, Village: Navghar, Vasai Road (W), Distt.: Palghar, Maharashtra- 401 202



M/S VIDYA VARDHINI

M/S SHILP SADHANA ARCHITECTS

Prepared By

## M/s Green Care Solutions

217, Ambika Commercial Complex, Navghar, Vasai Road (E), Palghar : 401 210

Te.: 0250-2391299, Mob: +91- 9975975645 /08976011736

e-mail:gcsolutions@rediffmail.com



# Check List for OC

Sr No.	Document For OC	Check Appropriate Box			
		Yes	No	Not applicable	
1	Completion Certificate of RWH system	٧			
2	No. of Rain Water Downtake pipes & final location of pipe	4			
3	Final Location of Fire hydrant & Pipe line	٧			
4	Final Location of Septic tank / STP	√			
5	Final Layout Plan with location of RWH unit	1			
6	Final Section / Technical drawing of RWH unit	4			
7	CD with Geo tag of RWH unit with all documents photographs & Video Shooting.	1			





Ref. No.: GCS/RWH/015/2017

To, Date: 29/05/2017

The DDTP, VVCMC,

Virar (E), Dist: Palghar.

SUB: Completion Certificate for Rain Water Harvesting System for proposed Art Science Building & Polytechnic Workshop Building S. No. 20, 21 (P), 22 & 23,

Village: Navghar, Taluka-Vasai, Dist.: Palghar.

REF: BP-968/W/1685

We hereby certify that the Rain Water Harvesting System as per our design is completed in above cited building to our satisfaction and as per the guidelines given under TPB-432001/2133/CR-230/01/UD-11, dated 10<sup>th</sup> March, 2005 and in the Notification No.: TPB-4307/396/CR-124/2007/UD-11, dated 6<sup>th</sup> June, 2007 issued by Government of Maharashtra.

The scrutiny sheet in standard format duly signed along with necessary documents, photographs, CD, Google image with latitude & longitude of site under reference is attached herewith for your perusal & ready reference. The completed work may please be accepted.

Thanking you,

Yours Faithfully,

FOR GREEN CARE SOLUTIONS

MR. SOURABH JAISWAR

Reg. No.: PRWHC-005 C.C. to Architect / L.E.

217, Ambika Commercial Complex, 2nd Floor, Navghar, Vasai Road (E), Dist. Thane, Maharash ra - 401 210 Tel: 0250-239 1299 Cell: +91-9975 975 645 / 9664 450 939 E-mail: gcsolutions@redffmail.com







#### A. RUN OFF (DISCHARGE) CALCULATION

Ħ	Type of Surface	Catchments Area	Area (Sq. m) (A)	Run off Coefficient (C)	fall (m/hr)	Discharge (Run off) (Q=CIA) m <sup>3</sup>	Total (m³) Discharge (Q)
-	RCC	Terrace area	3800	0.90	0.025	0.9 x 0.025 x 3800	85.5
1.					0.025	0.85 x 0.025x 2700	57.30
2.	Paved Block	Pavement area	2700	0.85	0.025	0.83 X 0.023X 2700	

## B. VOLUME OF TERRACE WATER

 $= 85.5 \, \text{m}^3/\text{hr}$ Total Storm Water Flow

Considering 03 minute of retention time, volume = 4.2 m<sup>3</sup>

=  $(1 \text{ m } \emptyset \text{ x } 4.5 \text{ m depth})$ Dimension of Ring Well

= 2.0 No of provided Ring Well

# C. VOLUME OFSURFACE WATER

 $= 57.3 \text{ m}^3/\text{hr}$ Total Storm Water Flow


Considering 05 minute of retention time, volume = 4.70 m<sup>3</sup>


= 04, Size (1.2 x 1.0 x 1.6) m No of percolation Pit

Storm water of paved area diverted into percolation Pit for ground water recharge.













RING WELL -1



RING WELL WITH FLUSH VALVE CHAMBER



RECHARGE PIT -1



VERTICAL FLUSH VALVE



RING WELL - 2




RECHARGE PIT- 2

RAIN WATER HARVESTING SNAPS










Recharge Pit 1, Roof water turned to near open well by pipe



Recharge Pit 2, Roof water turned through pipe for the water percolation in the campus



Recharge Pit 3, the flow of rainwater turned through pipe for the water percolation in the campus



Recharge Pit 4, the flow of rainwater turned through pipe near the open well.

